

圆管涵工程数量表

S4-3

宾阳县新桥镇新桥社区六谢村仙女山道路项目

序号	中心桩号	涵洞角度 (度)	孔数-跨径 (孔-米)	涵长 (米)	进出口形式		工 程 数 量									
							洞 身									
					进口	出口	C30号管身砼 (m³)	C20管基 (m³)	砂砾垫层 (m³)	管节钢筋 (kg)				沥青麻絮 沉降缝、 接头填充 (m²)	沥青防水层 (二层) (m²)	接头两层 15cm宽 沥青油毡 (m²)
										HPB300			HRB400			
										Φ6.5	Φ8	Φ10	Φ10			
1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17
1	K0+141	90	1-Φ0.5	5.0	一字墙	一字墙	0.53	2.25	1.22	36.40				0.53		0.60
2	K0+228	90	1-Φ0.5	5.0	一字墙	一字墙	0.53	2.25	1.22	36.40				0.53		0.60
3	K0+352	90	1-Φ0.5	5.0	一字墙	一字墙	0.53	2.25	1.22	36.40				0.53		0.60
4	K0+568	90	1-Φ0.5	5.0	一字墙	一字墙	0.53	2.25	1.22	36.40				0.53		0.60
5	K0+690	90	1-Φ0.5	5.0	一字墙	一字墙	0.53	2.25	1.22	36.40				0.53		0.60
6	K0+796	90	1-Φ0.5	5.0	一字墙	一字墙	0.53	2.25	1.22	36.40				0.53		0.60
7	K0+888	90	1-Φ0.5	5.0	一字墙	一字墙	0.53	2.25	1.22	36.40				0.53		0.60
8	K0+993	90	1-Φ0.5	5.0	一字墙	一字墙	0.53	2.25	1.22	36.40				0.53		0.60
9	K1+139	90	1-Φ0.75	5.0	一字墙	一字墙	0.15	7.40	1.51	84.40				2.58		3.00
10	K1+164	90	1-Φ0.5	5.0	一字墙	一字墙	0.53	2.25	1.22	36.40				0.53		0.60
11	K1+213	90	1-Φ0.75	5.0	一字墙	一字墙	0.15	7.40	1.51	84.40				2.58		3.00
12	K1+576	90	1-Φ0.75	5.0	一字墙	一字墙	0.15	7.40	1.51	84.40				2.58		3.00
13	K1+694	90	1-Φ0.5	5.0	一字墙	一字墙	0.53	2.25	1.22	36.40				0.53		0.60
14	K1+771	90	1-Φ0.5	5.0	一字墙	一字墙	0.53	2.25	1.22	36.40				0.53		0.60
合计				70.0			6.2	47.0	18.0	653.6				13.6		15.6

编制: 张冲

复核: 杜刚军

