

路基土石方数量计算表						
西林县足别瑶族苗族乡平木村央报屯至那朋油茶产业基地道路硬化工程						S3-9
公路 段						
桩号	面积(平方米)		距离	挖方数量	填方数量	备注
	挖方	填方	(m)	(立方米)	(立方米)	
K0+000.000	0.510	0.085				
K0+020.000	1.816	0.000	20.000	23.26	0.85	
K0+040.000	2.158	0.000	20.000	39.74	0.00	
K0+060.000	1.990	0.000	20.000	41.48	0.00	
K0+080.000	1.660	0.059	20.000	36.50	0.59	
K0+100.000	1.775	0.000	20.000	34.35	0.59	
K0+120.000	1.532	0.000	20.000	33.08	0.00	
K0+140.000	2.164	0.000	20.000	36.96	0.00	
K0+160.000	2.190	0.002	20.000	43.55	0.02	
K0+180.000	2.235	0.005	20.000	44.25	0.07	
K0+200.000	1.913	0.097	20.000	41.48	1.01	
K0+220.000	0.837	0.161	20.000	27.50	2.58	
K0+240.000	1.102	0.073	20.000	19.39	2.34	
K0+260.000	1.034	0.000	20.000	21.36	0.73	
K0+280.000	1.454	0.000	20.000	24.88	0.00	
K0+300.000	0.343	0.080	20.000	17.97	0.80	
K0+320.000	1.004	0.231	20.000	13.46	3.11	
K0+340.000	1.003	0.066	20.000	20.07	2.96	
K0+360.000	0.831	0.079	20.000	18.34	1.45	
K0+380.000	1.211	0.000	20.000	20.42	0.79	
K0+400.000	1.272	0.010	20.000	24.83	0.10	
K0+420.000	0.302	0.247	20.000	15.74	2.57	
K0+440.000	1.536	0.000	20.000	18.38	2.47	
K0+460.000	0.478	0.198	20.000	20.14	1.98	
K0+480.000	1.605	0.000	20.000	20.82	1.98	
K0+500.000	0.880	0.004	20.000	24.85	0.04	
K0+520.000	1.304	0.004	20.000	21.84	0.08	
K0+540.000	0.370	0.330	20.000	16.74	3.34	
K0+560.000	0.400	0.218	20.000	7.70	5.48	
K0+580.000	1.529	0.000	20.000	19.30	2.18	
K0+600.000	1.787	0.000	20.000	33.17	0.00	
K0+620.000	1.827	0.000	20.000	36.14	0.00	
K0+640.000	2.694	0.019	20.000	45.21	0.19	
K0+660.000	1.263	0.225	20.000	39.57	2.44	
K0+680.000	0.465	0.067	20.000	17.28	2.92	
K0+700.000	1.947	0.010	20.000	24.13	0.77	
K0+720.000	1.946	0.000	20.000	38.93	0.10	
K0+740.000	0.493	0.088	20.000	24.39	0.88	
K0+760.000	1.501	0.226	20.000	19.94	3.14	

路基土石方数量计算表						
西林县足别瑶族苗族乡平木村央报屯至那朋油茶产业基地道路硬化工程						S3-9
公路 段						
桩号	面积(平方米)		距离	挖方数量	填方数量	备注
	挖方	填方	(m)	(立方米)	(立方米)	
K0+780.000	1.916	0.213	20.000	34.17	4.39	
K0+800.000	2.070	0.000	20.000	39.86	2.13	
K0+820.000	0.692	0.035	20.000	27.62	0.35	
K0+840.000	0.883	0.070	20.000	15.74	1.05	
K0+860.000	2.201	0.380	20.000	30.84	4.51	
K0+880.000	2.505	0.008	20.000	47.06	3.88	
K0+900.000	1.755	0.171	20.000	42.59	1.79	
K0+920.000	0.501	0.263	20.000	22.56	4.34	
K0+940.000	0.936	0.309	20.000	14.37	5.73	
K0+960.000	1.175	0.000	20.000	21.11	3.09	
K0+980.000	1.125	0.000	20.000	23.00	0.00	
K1+000.000	0.502	0.424	20.000	16.27	4.25	
K1+020.000	0.441	0.087	20.000	9.42	5.12	
K1+040.000	1.609	0.000	20.000	20.49	0.87	
K1+060.000	1.092	0.068	20.000	27.01	0.68	
K1+080.000	1.546	0.576	20.000	26.39	6.44	
K1+100.000	1.195	0.000	20.000	27.41	5.76	
K1+120.000	0.319	0.115	20.000	15.14	1.15	
K1+140.000	0.855	0.000	20.000	11.74	1.15	
K1+160.000	1.188	0.096	20.000	20.43	0.96	
K1+180.000	0.807	0.158	20.000	19.95	2.55	
K1+200.000	0.467	0.511	20.000	12.75	6.69	
K1+220.000	2.315	0.000	20.000	27.82	5.11	
K1+240.000	1.335	0.255	20.000	36.50	2.55	
K1+260.000	1.836	0.003	20.000	31.71	2.59	
K1+280.000	0.935	0.188	20.000	27.71	1.91	
K1+300.000	1.036	0.541	20.000	19.71	7.29	
K1+320.000	2.331	0.036	20.000	33.67	5.77	
K1+340.000	2.436	0.012	20.000	47.68	0.48	
K1+360.000	2.928	0.095	20.000	53.65	1.07	
K1+380.000	1.677	0.000	20.000	46.05	0.95	
K1+400.000	1.515	0.150	20.000	31.92	1.50	
K1+420.000	0.884	0.196	20.000	23.99	3.46	
K1+440.000	1.001	0.002	20.000	18.86	1.98	
K1+460.000	0.504	0.361	20.000	15.06	3.63	
K1+480.000	1.261	0.000	20.000	17.66	3.61	
K1+500.000	0.494	0.154	20.000	17.55	1.54	
K1+520.000	0.889	0.195	20.000	13.83	3.49	
K1+540.000	0.453	0.107	20.000	13.42	3.01	

路基土石方数量计算表						
西林县足别瑶族苗族乡平木村央报屯至那朋油茶产业基地道路硬化工程						S3-9
公路 段						
桩号	面积(平方米)		距离	挖方数量	填方数量	备注
	挖方	填方	(m)	(立方米)	(立方米)	
K1+560.000	0.201	0.197	20.000	6.54	3.04	
K1+580.000	0.324	0.202	20.000	5.26	3.99	
K1+600.000	1.106	0.211	20.000	14.30	4.13	
K1+620.000	0.865	0.016	20.000	19.71	2.27	
K1+640.000	0.936	0.021	20.000	18.01	0.37	
K1+660.000	0.790	0.050	20.000	17.25	0.71	
K1+680.000	1.698	0.000	20.000	24.87	0.50	
K1+700.000	1.875	0.000	20.000	35.72	0.00	
K1+720.000	1.750	0.012	20.000	36.25	0.12	
K1+740.000	2.596	0.343	20.000	43.46	3.55	
K1+760.000	0.907	0.207	20.000	35.03	5.50	
K1+780.000	1.707	0.042	20.000	26.14	2.48	
K1+800.000	0.972	0.392	20.000	26.79	4.34	
K1+820.000	0.844	0.024	20.000	18.16	4.16	
K1+840.000	1.781	0.008	20.000	26.25	0.31	
K1+860.000	0.977	0.018	20.000	27.58	0.26	
K1+880.000	1.473	0.205	20.000	24.49	2.24	
K1+900.000	1.242	0.000	20.000	27.14	2.05	
K1+920.000	0.282	0.143	20.000	15.24	1.43	
K1+940.000	0.545	0.039	20.000	8.28	1.83	
K1+960.000	0.658	0.014	20.000	12.03	0.53	
K1+980.000	0.231	0.410	20.000	8.89	4.24	
K2+000.000	1.087	0.000	20.000	13.18	4.10	
K2+020.000	0.627	0.023	20.000	17.14	0.23	
K2+040.000	0.650	0.052	20.000	12.77	0.75	
K2+060.000	1.206	0.030	20.000	18.55	0.83	
K2+080.000	1.293	0.000	20.000	24.98	0.30	
K2+100.000	0.621	0.034	20.000	19.13	0.34	
K2+120.000	0.764	0.104	20.000	13.85	1.37	
K2+140.000	0.204	0.456	20.000	9.68	5.60	
K2+160.000	1.251	0.000	20.000	14.54	4.56	
K2+180.000	1.103	0.000	20.000	23.54	0.00	
K2+200.000	0.804	0.153	20.000	19.07	1.53	
K2+220.000	0.592	0.013	20.000	13.96	1.66	
K2+240.000	1.641	0.006	20.000	22.33	0.20	
K2+260.000	1.375	0.000	20.000	30.16	0.06	
K2+280.000	0.956	0.060	20.000	23.31	0.60	
K2+300.000	1.338	0.160	20.000	22.94	2.20	
K2+320.000	2.642	0.000	20.000	39.80	1.60	

路基土石方数量计算表						
西林县足别瑶族苗族乡平木村央报屯至那朋油茶产业基地道路硬化工程						S3-9
公路 段						
桩号	面积(平方米)		距离	挖方数量	填方数量	备注
	挖方	填方	(m)	(立方米)	(立方米)	
K2+340.000	1.096	0.122	20.000	37.38	1.23	
K2+360.000	2.112	0.000	20.000	32.08	1.22	
K2+380.000	0.669	0.014	20.000	27.81	0.14	
K2+400.000	1.982	0.000	20.000	26.52	0.14	
K2+420.000	2.625	0.020	20.000	46.08	0.20	
K2+440.000	1.385	0.100	20.000	40.10	1.20	
K2+460.000	1.036	0.015	20.000	24.21	1.15	
K2+480.000	1.131	0.019	20.000	21.67	0.34	
K2+500.000	1.112	0.442	20.000	22.43	4.61	
K2+520.000	1.971	0.000	20.000	30.83	4.42	
K2+540.000	1.223	0.155	20.000	31.94	1.55	
K2+560.000	2.506	0.041	20.000	37.29	1.97	
K2+580.000	1.646	0.069	20.000	41.52	1.11	
K2+600.000	1.039	0.645	20.000	26.84	7.14	
K2+620.000	1.698	0.000	20.000	27.36	6.45	
K2+640.000	0.397	0.245	20.000	20.94	2.45	
K2+660.000	1.462	0.000	20.000	18.59	2.45	
K2+680.000	1.560	0.000	20.000	30.22	0.00	
K2+700.000	0.421	0.369	20.000	19.81	3.69	
K2+720.000	0.390	0.141	20.000	8.12	5.10	
K2+740.000	0.822	0.017	20.000	12.13	1.58	
K2+760.000	0.750	0.079	20.000	15.72	0.96	
K2+765.262	0.847	0.027	5.262	4.20	0.28	
合计	总挖方=3450.00立方米 总填方=288.70立方米					
计算:	复核:			日期:		